

Project Roland

Retrofitting a Cleanroom to achieve ISO Class 3: *A Case Study*

John R. Weaver
Delphi Delco Electronics Systems

Agenda


- Introduction
- Facility Modifications
- Utility Modifications
- New Tool Set
- Construction Project
- Certification and Commissioning

Existing Cleanroom

- 60,000 square feet of Class 10 ($0.3\mu\text{m}$)
- Designed 1984, Constructed 1985
- Small chases, accessible only from cleanroom
- Sidewall air return, upflow through chase
- Ballroom in diffusion area, penetrations through waffle slab

J. R. Weaver

Layout of Fab III



J. R. Weaver

Photos of Fab III



J. R. Weaver

Project Goals

- Overall Goal
 - ◆ Successfully implement a **new wafer size** and **process technology** that require a **new tool set** and a **higher level of cleanliness**
- Individual Goals
 - ◆ Achieve ISO Class 3 cleanroom conditions
 - ◆ Perform clean-installation of new tool set
 - ◆ Minimize construction cost
 - ◆ Bring new process into operation as rapidly as practical

J. R. Weaver

Process Capability Improvement

ASIC fab with several process families and hundreds of part numbers

- Minimum feature size
 - ◆ 1.0 μm => 0.75 μm
- Wafer size
 - ◆ 5-inch => 8-inch

J. R. Weaver

Boundary Conditions

- Maintain operation of existing fab
 - ◆ Minimum utility interruptions
 - ◆ No cleanliness impact
 - ◆ Minimum vibration transmission
- No increase in cleanroom footprint
- Turnaround space must be in existing cleanroom

J. R. Weaver

Strategy

- Facility Modification
- Utility Upgrade
- New Tool Set
- Clean-Construction Protocol
- Upgrade Operational Protocol
in Entire Facility

J. R. Weaver

Agenda

- Introduction
- **Facility Modifications**
- Utility Modifications
- New Tool Set
- Construction Project
- Certification and Commissioning
- New Operational Protocol

J. R. Weaver

Wall Layout

- Minimize area under filter
- Maximize chase sizes
- Bulkhead-mount equipment

J. R. Weaver

Small Cleanroom Aisles

- Activities in aisle
 - ◆ Support functions only
 - ◆ Operator traffic
- Comprehend small cleanroom population
- All computer monitors in chases
 - ◆ Cleanliness
 - ◆ Cleanroom footprint eliminated

J. R. Weaver

Chase Configuration Before and After



Small chase, big bay
Original facility design



Big chase, small bay
Project Roland J. R. Weaver

Bay Configuration *Before and After*



Wide bay with equipment
in cleanroom area
Original facility design



Narrow bay,
minimal equipment
Project Roland J. R. Weaver

Ion Implanter *Before and After*



Ion Implanters in cleanroom
Original facility design



Ion Implanter recessed in chase
Project Roland

J. R. Weaver

Filter replacement

■ Original filters

- ◆ Particle-board frame
- ◆ Foam gaskets
- ◆ Fiberglass medium
- ◆ HEPA-rated (99.97% @ 0.3 μ m)
- ◆ 15-years old

■ New filters

- ◆ Aluminum frame (custom extrusion)
- ◆ Gel seal built into housing
- ◆ Expanded PTFE medium
- ◆ Low-outgassing potting
- ◆ ULPA-rated (99.999% @ 0.1 μ m)

J. R. Weaver

Raised Floor vs. Solid Floor

- Virtually all ISO Class 3 facilities are built with a raised floor
 - ◆ Simplified air handling
 - ◆ Better unidirectionality
- Retrofit would be awkward
 - ◆ Low ceiling height or complex overhead rearrangement
 - ◆ Step-up from other areas of cleanroom and from perimeter aisle
 - ◆ Serious problems in movement of equipment

J. R. Weaver

Retain Solid Floor

- Minimizes expense
- Simplifies logistics
- Unidirectionality is biggest challenge
 - ◆ Imaginative equipment installation
 - ◆ Fine-tuning of airflow

J. R. Weaver

"Fine Tuning" Airflow

- Air return through equipment
- "Raising" equipment
- Maximizing low-return space
 - ◆ Door panels
 - ◆ Half-size walls (would be blanks)
- Varying supply velocity as required
 - ◆ "Blending" changes in velocity

J. R. Weaver

Centura™ System "On Blocks"

Note blocks used to raise system and allow increased air-return area



J. R. Weaver

Agenda

- Introduction
- Facility Modifications
- **Utility Modifications**
- New Tool Set
- Construction Project
- Certification and Commissioning
- New Operational Protocol

J. R. Weaver

Baseline Utility Study

- Capacity
 - ◆ Model existing tool set
 - ◆ Compare to actual usage
 - ◆ Model new tool set
 - ◆ Project new usage level
- Quality
 - ◆ Applies to process gasses
 - ◆ Point of generation / Storage location
 - ◆ Building entry point
 - ◆ Point of use

J. R. Weaver

Quality Metrics

- Particle concentration
- Moisture level
- Oxygen concentration
- Metals

J. R. Weaver

Add New Quality Level For Process Gasses

- Additional process system
 - ◆ Fed by existing high-purity mains
 - ◆ Adds to utility-grade and high-purity-grade systems
- Used selectively
 - ◆ Based on engineering judgement
 - ◆ Wafer-contact fluids only
 - ◆ Critical process tools

J. R. Weaver

Certified Quality Of Installation

- Third-party certifier
 - ◆ Special training for installers
 - ◆ Twice-per-shift weld certification
- State-of-art fabrication methods
 - ◆ New welding equipment
 - ◆ Dedicated fabrication cleanroom
 - ◆ Special purging methods/materials
- Commissioning of each line

J. R. Weaver

Agenda

- Introduction
- Facility Modifications
- Utility Modifications
- **New Tool Set**
- Construction Project
- Certification and Commissioning
- New Operational Protocol

J. R. Weaver

New Tools

- 8-inch wafer capability
- Bulkhead mounting (most)
- Low particle additions
 - ◆ Wafer
 - ◆ Room
- High MTBF

J. R. Weaver

Refurbished Tools

- Refurbished by manufacturer
 - ◆ In factory
 - ◆ On site
- Same specifications as new tools

J. R. Weaver

Agenda

- Introduction
- Facility Modifications
- Utility Modifications
- New Tool Set
- **Construction Project**
- Certification and Commissioning
- New Operational Protocol

J. R. Weaver

Construction Goals

- Maintain operation of existing cleanroom
 - ◆ 24-7 operation
 - ◆ Class 10 environment
- Minimize downtime of relocated equipment
 - ◆ Schedule around production needs
 - ◆ Maximize resource allocation when tool taken out of service
- Final cleanliness is paramount
- Cost control and efficient construction techniques

J. R. Weaver

Developing the Task List

- Train construction workforce
- Relocate equipment in construction area that will be used elsewhere in the fab
- Isolate construction area
- Demo construction area
- Relocate walls as required
- Perform filter modifications and replacement
- Complete utility fit-up
- Install equipment
- Perform final cleaning
- Commission cleanroom
- Commission equipment

J. R. Weaver

Chronological and Physical Phasing

- Develop completion schedule by area
 - ◆ Tool delivery
 - ◆ Physical access to areas
 - ◆ Process needs
- Develop contingencies for delays
 - ◆ Tool delivery
 - ◆ Construction
- Utilize critical-path management techniques

J. R. Weaver

Phasing of Cleanliness

- Determine contamination caused by various stages of construction
- Build protocol sequence based on
 - ◆ Task list
 - ◆ Contamination generated
 - ◆ Cleanliness needs
- Develop training and enforcement plans

J. R. Weaver

Cleanliness Phases

- | | |
|---|---|
| ■ Tool Relocation <ul style="list-style-type: none">◆ Full gowning and protocols | ■ Fit-up <ul style="list-style-type: none">◆ Frocks, hair covers, gloves◆ Highly restricted practices |
| ■ Demolition <ul style="list-style-type: none">◆ No gowning requirements | ■ Equipment Installation <ul style="list-style-type: none">◆ Full jumpsuits - polyester◆ Cleanroom protocols |
| ■ Wall and Filter Modification <ul style="list-style-type: none">◆ No gowning requirements◆ Restricted practices | ■ Commissioning and Punch List <ul style="list-style-type: none">◆ Full production gowning and protocols |

J. R. Weaver

Cleaning After Construction

- Cleaning follows protocol levels
- By end of construction, little to no visible contamination
- Intensive training of cleaning personnel
- Final clean is iterative
 - ◆ Vacuum, mop/wipe, vacuum
 - ◆ Measure with wipers/blacklight and Q3
 - ◆ Repeat as required

J. R. Weaver

Agenda

- Introduction
- Facility Modifications
- Utility Modifications
- New Tool Set
- Construction Project
- **Certification and Commissioning**
- New Operational Protocol

J. R. Weaver

Filter Certification

- Media leakage
 - ◆ PSL challenge
- Seal leakage
 - ◆ Gel seal
 - ◆ Gasket seal
- Flow

J. R. Weaver

Cleanroom Certification

- Parallelism
 - ◆ Continue “fine tuning” of airflow
- Airflow
 - ◆ To “custom velocity” map
- Cleanliness

J. R. Weaver

Utility Certification

- Evaluate at sample locations to established specification
 - ◆ Quality
 - ◆ Pressure
 - ◆ Volume

J. R. Weaver

Tool Certification

- Processing performance criteria
- Particle additions to wafers
- Airflow contributions
 - ◆ Positive and negative
 - ◆ Hand-in-glove with parallelism
- Particle additions to room
- MTBF

J. R. Weaver

Agenda

- Introduction
- Facility Modifications
- Utility Modifications
- New Tool Set
- Construction Project
- Certification and Commissioning
- **New Operational Protocol**

J. R. Weaver

Gowning Procedure

- Improved pregowning
- Better training for gowning process
 - ◆ Retrained entire workforce
 - ◆ Produced video for occasional cleanroom personnel
 - ◆ Institutionalized processes
- Increased enforcement
 - ◆ Especially during first week
 - habit formation
 - supervised gowning

J. R. Weaver

Cleanroom Garments

- PTFE-laminate garments
 - ◆ Significant improvement in cleanliness
 - ◆ Lower contaminant “add-ons”
- Garments assigned to individuals
- Upgraded laundry facilities

J. R. Weaver

Cleanroom Cleaning

- Instituted new cleaning procedures throughout fab
- Upgraded cleaning materials and equipment
- Retrained cleaning workforce

J. R. Weaver

Protocol Refresher Training

- Retrained workforce on cleanliness needs and product impact
- Reasserted importance of protocol compliance
- Stressed operator empowerment to enforce protocols
- Reiterated critical protocols

J. R. Weaver

Protocol Enforcement

- Retrained leadership team
 - ◆ Cleanliness needs/product impact
 - ◆ Importance of protocol compliance
 - ◆ Criticality of personal example
- Enhanced enforcement during beginning of program
 - ◆ Setting positive habits
 - ◆ Communicating seriousness of intent to operators

J. R. Weaver

Results

- Certified to ISO Class 3
- Process capability projections exceeded
- Yield far above targets